

Name	Item Description		volume
12	10		629.949
p4 footing	2,500 Strength after 28 Days		4.933
p3 footing	2,500 Strength after 28 Days		10.927
p2 footing	2,500 Strength after 28 Days		3.978
p footing	2,500 Strength after 28 Days		4
M Footing	2,500 Strength after 28 Days		62.161
M Footing	2,500 Strength after 28 Days		28.716
M Footing	2,500 Strength after 28 Days		230.35
Basement slab			135.259
Basement slab fr			135.781
fnt. p4 footing	2,500 Strength after 28 Days		4.933
fnt. p2 footing	2,500 Strength after 28 Days		3.978
fnt p4 footing	2,500 Strength after 28 Days		4.933
	Total Porch Footing	cubic ft	308.722
		Yards	11.434
	Main Foundation Footing	cubic ft	321.227
		yards	11.897
	Total foundation volume		629.949
	Total concrete cost	@ \$110.00 per yard	2566.46

Layer/Class/Wall/Type	Height	Length	Qty	Linear Amt	Remarks
Mod-Floor-1					
Default					
Frame 1					
Studs	7'9"		6	46'6"	
Sill Stock					
Plate Stock				12'2 3/4"	
Block Stock				5'7 1/8"	
Frame 2					
Studs	7'9"		6	46'6"	
Sill Stock					
Plate Stock				13'1"	
Block Stock				5'8 1/4"	
Frame 3					
Studs	7'9"		9	69'9"	
Sill Stock					
Plate Stock				27'2"	
Block Stock				12'5"	
Frame 4					
Studs	7'9"		7	54'3"	
	6'9 3/4"		2	13'7 1/2"	
	7 3/4"		2	1'3 1/2"	
Header 1	3 1/2"	3'5 1/2"			Ht. not calculated for load
Sill Stock				12'3 1/2"	
Plate Stock				24'4 1/2"	
Block Stock				7'8 3/8"	
Frame 5					
Studs	7'9"		2	15'6"	
	6'9 3/4"		2	13'7 1/2"	
	5 3/4"		2	11 1/2"	
Header 1	5 1/2"	4'5 1/2"			Ht. not calculated for load
Sill Stock				16'8 3/4"	
Plate Stock				8'9 3/8"	
Block Stock					
Frame 6					
Studs	7'9"		16	124'0"	
	6'8 3/4"		2	13'5 1/2"	
	6'8 3/4"		2	13'5 1/2"	
	8 3/4"		2	1'5 1/2"	
	6 3/4"		2	1'1 1/2"	
Header 1	3 1/2"	2'7 1/2"			Ht. not calculated for load
Header 2	5 1/2"	5'7 1/2"			Ht. not calculated for load
Sill Stock				22'7"	
Plate Stock				40'9 5/8"	
Block Stock				9'7"	